

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


29-5-29W

Company- SINCLAIR OIL & GAS CO.  
 Farm- L. Shaw No. 1

SEC. 29 T. 5 R.29W  
 NW SW SE

Total Depth. 4220'  
 Comm. 9-2-60 Comp. 9-14-60  
 Shot or Treated.  
 Contractor. K & E Drlg.  
 Issued. 2-11-61

County Decatur  
 KANSAS



Elevation. 2762' GL

Production. Dry

CASING:

8 5/8" 294' cem w/250 sx.  
 5 1/2" 4112' cem w/250 sx.

Figures Indicate Bottom of Formations.

cellar & clay	70
sand	145
shale	1425
shale & shells	2075
shale & strks anhy	2145
shale & red bed	2232
Anhydrite	2245
shale & shales	2497
Anhydrite	2536
shale	2550
shale & shells	2760
shale & lime	2900
lime & shale	3184
lime	3895
chert	3903
lime	4220
Total Depth	

TOPS: SCOUT

Heebner	3805
Toronto	3835
Lansing	3850
"D" Zone	3886
"G" Zone	3934
"H" Zone	3964
"J" Zone	3998
"K" Zone	4024
"L" Zone	4045
Cherokee Lime	4196