

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


17-5-30W

Company- THE DERBY OIL CO.
Farm- Skiles No. 1

SEC. 17 T. 5 R. 30W
SE SE SW
330' fr SL, 2310' fr WL

Total Depth. 4600
Comm. 9-28-54 Comp. 10-13-54
Shot or Treated.
Contractor. Schafer Drilling Co.
Issued. 12-25-54

County Decatur
KANSAS



Elevation. 2913 DF (est.)

CASING:

8 5/8 348' w/ 200 sx cmt.

Production. Dry

Figures indicate Bottom of Formations.

sand	200
shale & shells	348
shale	825
shale & shells	1625
sand, shale & shells	2100
shale & shells	2268
anhydrite	2308
shale & shells	2980
lime & shale	3070
shale & shells	3360
lime & shale	3960
lime	4197
shale	4210
lime & shale	4475
lime	4500
lime & chert	4530
lime, chert & shale	4590
lime	4600 RTD
Total Depth	

SCHLUMBERGER TOPS:

Heebner	3917
Lansing	3965
Marmaton	4196
Mississippi chert	4485
Arbuckle	4578

DST #1: 3948-4000, open 1 hr. Fair
blow 1 hr. rec. 130' muddy SW, BHP
1005#, IFP 0#, FFP 70#

DST #2: 4118-4160, open 45 min. rec.
15' VSIOCM, BHP 510#

Ran Schlumberger Etc. log