

KANSAS DRILLERS LOG

15-039-20388  
25-5-30W

API No. 15 — 039 — 20,388  
County Number

S. 25 T. 5S R. 30  
Loc. 225' FEL - 91' FSL  
County

Operator  
Cities Service Oil Company

Address  
700 Sutton Place Bldg., 209 E. William, Wichita, Kansas


Well No. 3 SWD Lease Name Davis "E"

Footage Location  
91 feet from (W) (S) line 225 feet from (E) (N) line

Principal Contractor Red Tiger Drilling Co. Geologist Well Site - None

Spud Date March 6, 1977 Total Depth 2622' P.B.T.D. 2582'

Date Completed March 21, 1977 Oil Purchaser



Elev.: Gr. 2825'  
DF 2827' KB 2830'

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	28#	279'	Common	225	2% Gel + 3% C. C.
Injection	7-7/8"	5-1/2"	14#	2614'	HowcoLite	400	10# Gilsonite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		2320-2380'
TUBING RECORD					
Size	Fiberglass	Setting depth	Packer set at		
2-7/8" OD			2292'		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production 3-21-77	Producing method (flowing, pumping, gas lift, etc.) Salt Water Disposal				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Cities Service Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

3 SWD

Lease Name

Davis "E"

Salt Water Disposal

S 25 T 5S R 30 ~~W~~  
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<del>See Attached</del>				
Surface Clay & Shale	0	280		
Shale	280	438		
Hard Sand	438	444		
Shale	444	1900		
Shale, Sand, Shale	1900	2202		
Shale	2202	2570		
Anhydrite	2570	2595		
Anhydrite - Shale	2595	2615		
RTD		2615		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*E. W. Peterman*

Signature

E. W. Peterman

Region Operations Manager

Title

March 29, 1977

Date

92-2-30M