

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

4-5-31W


Company. AMERADA PETROLEUM
Farm. G. W. Chance No. 1

SEC. 4 T. 5 R.31W
C SW SW

Total Depth. 4218'
Comm. 5-3-61 Comp. 5-19-61
Shot or Treated.
Contractor. Jelly Reaves Drig.
Issued. 7-29-61

County Rawlins

KANSAS



Elevation. 2946'

Production. Dry

Figures Indicate Bottom of Formations.

shale & sand	215
shale	1560
shale & shells	1795
shale	2440
lime	2455
shale	2675
Anhydrite & shale	2850
shale	3130
shale w/lime strks	3320
red bed & lime	3430
shale	3490
shale & lime	3610
lime	3675
shale & sand	3800
lime	4218
Total Depth	

TOPS: SCOUT	
Heebner	3923
Toronto	3956
Lansing	3970
Base Kansas City	4200

Dst #1 3984-4015 (Lans) 90", FB, Rec 560' MCSW,
no oil, IFP 30#, FFP 265#, FBHP 1305#/90"
DST #2 4133-68 (Lans) up 90" WB/died/12", Rec 10'M,
IFP 0#, FFP 0#, FBHP 620#90"

Ran log D & A 5/15/1961 (top card).