

COPY

RAYMOND OIL COMPANY, INC.

P. O. BOX 48788

ONE MAIN PLACE - SUITE 900

TELEPHONE 316-267-4214

WICHITA, KANSAS 67201

May 25, 1993

Kansas Corporation Commission  
Attn: Don V. Rider

Re: DST on the #1 Briney Farms:

=====

DST #1 4159 - 4206 (Toronto)  
30" 45" 30" 45"

IF: Week blow 1" in bucket  
FF: No blow  
REC: 20' Mud  
IFP: 30-66#  
FFP: 30-77#  
ISIP: 1171#  
FSIP: 1105  
Temp: 111°

=====

DST #2 4197-4319 (Lansing)  
30" 45" 45" 45"

IF: Bottom bucket in 21"  
FF: Bottom bucket in 30"  
REC: 67'0 CM (92% Md 8%O)  
125'0 & WCM (70% md 25% W 5%O)  
410'0 & MCW (45% md 52% W 3%O)

-----

602' Total fluid  
IFP: 55-142#  
FFP: 165-265#  
ISIP: 1237#  
FSIP: 1171#  
Temp: 112°

=====

DST #3 4197-4319 (Pawnee)  
30" 60" 45" 75"

IF: Bottom bucket in 30 seconds  
FF: GTS at end of first shut-in  
REC: 3413' CGO (70%O 30%G)  
IFP: 729-1010#  
FFP: 1110-1210#  
ISIP: 1260#  
FSIP: 1270#                      Temp 148°

RECEIVED  
STATE CORPORATION COMMISSION

MAY 26 1993

KANSAS CORPORATION COMMISSION  
Wichita, Kansas