

15-023-20028 (COPY) 3-5-42w

KANSAS DRILLERS LOG

S. 3 T. 5s R. 42W XR W

API No. 15 _____ County _____ Number _____

Loc. NE/4

County Cheyenne

Operator
Murfin Drilling Company

Address
617 Union Center, Wichita, Ks 67202


Well No. 1 Lease Name WALZ

Footage Location
1320 feet from (N) line 1320 feet from (E) line NE/4

Principal Contractor Geologist
Murfin Drilling --

Spud Date Total Depth P.B.T.D.
11/30/76 1560' --

Date Completed Oil Purchaser
12/2/76 Not known at this time



Elev.: Gr. 3555' GL
DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24#	190'	60/40 Poz	225	2% Gel 3% CaCl
Production	7 7/8	4 1/2		1490'	Class A Latex 50/50 Poz	75 75	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	DP Jets	1311-16, 1303-08', 1293-98' & 1285-90'

TUBING RECORD

Size	Setting depth	Packer set at
1 1/2" tubing	1366'	--

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gallons 15% MCA	above perms

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
4/16/77	Flowing
RATE OF PRODUCTION PER 24 HOURS	Producing interval(s)
Oil _____ bbls. Gas 83.2 MCF Water _____ bbls. Gas-oil ratio _____ CFPB	1311-1290'
Disposition of gas (vented, used on lease or sold) VENTED DURING TEST - SHUT IN GAS WELL	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Murfin Drilling

3-5-42

TYPE OF WELL OIL, GAS, DRY HOLE, SWD, ETC. SI Gas well

Well No.

1

Lease Name

WALZ

S 3 T 5 S R 42 R W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
sub soil & sand/clay sand, shale shale shale w/sand & gyp shale RTD		125 225 950 1440 1560 1560		
No DST's were taken				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wm. S. Shropshire

Signature

Wm. S. Shropshire, Asst. Gen. Manager

Title

September 7, 1977

Date