


Total Depth. 3952'
Comm. 12-23-42 Comp. 2-1-43
Shot or Treated.
Contractor. H.B. Mabey Co.
Issued. 2-13-43

County. Mitchell



CASING:
12 1/4" 90'

Elevation. 1561 R_h

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	80	Hunton lime cherty	3512
shale & shells	265	lime sft porous	3555
sand	340	shale	3586
shale	440	<u>lime Viola</u>	3607
shale & shells	772	lime sft	3612
shale	840	lime	3643
anhydrite	880	dolomite	3645
shale	1200	lime	3695
red bed	1325	lime porous	3720
lime & shale	1380	lime hd	3765
lime	1410	shale green	3767
lime & shale	1480	lime	3850
lime brkn	1830	shale	3853
shale & shells	2121	lime	3860
lime Topeka	2170	shale, lime sand strks	3930
lime brkn	2295	<u>lime Arbuckle</u>	3952
shale red	2300	Total Depth.	
lime brkn	2355		
lime	2380		
shale & lime	2395		
shale red	2420		
shale	2490		
lime Kansas City	2578		
lime oolitic	2609		
lime	2684		
shale	2695		
lime	2700		
lime oolitic	2710		
shale	2718		
lime	2755		
shale	2772		
lime	2798		
lime porous	2810		
shale	2830		
lime	2838		
lime brkn	2853		
lime	2860		
shale sand strks	2900		
shale	2917		
lime	2920		
shale	2943		
lime	2946		
shale	2960		
shale sdy	2973		
shale red	2976		
shale sdy	3000		
Charokey shale	3050		

(-2025 v)

3586
1561
-2025

3512
3350
162

Viola 3586'
ARB 3930'

3930
1560
-2370

3350
3166
184
3166
3350