


don't rep't

State Ks. Field W.C.
 Company PHILLIPS County SHERMAN
 Farm LLANOS No. 1
 Sec. 10 Twp. 6 S Range 37 W

Spot CW/2 NW NE



Contractor

Remarks TITE HOLE

Comm. 4-2-58 Comp. 8-6-58
 Elev. DF 3483 GL KB TD 5001 PB 4260
 Pay 4804-12 gty 25.2°

pump I.P. 319 BOPD Press.
 Casing Record: 13 3/8" 7"
 20" 10 3/4" 4 1/2" 5000
 16" 8 5/8"

	Sample LOG	Log or Spk
DST 1100-1337 op.1'		Niobrara 1100
REC. 125' MUD + S.O.		WAB 3937
FP 154-185		Houston 4066
BHP 326/20"		TOP 4089
DST 4011-4121 op.1'		HB 4242
REC. 1930' MXW + 600' xw		TORO 4272
FP 470-1110		LAN-K.C. 4290
BHP 1180/20"		MARM 4548
DST 4197-4263 op.1'		CHERO. Is 4749
REC. 155' MXW + S.O.		MISS 4947
FP 87-208, BHP 1187/20"		
DST 4273-4330 op.1'		
REC. 300' WTR w/ S.O.		
PRESS. FAILED		
DST 4332-95 op.1'		
REC. 2000' MXW + 1000' SULEUR WTR		
FP 415-1280, BHP 1280/20"		
DST 4455-87 op.1', REC. 650' GASSY OIL +		
450' G + OCM (gty 33.5°), FP 69-452, IBHP 1381/20"		
DST 4594-4611 op. ? , REC. 720' GAS + 3290'		
GASSY OIL + 210' M + GCO (gty 29.8°), FP 198-1200		
BHP 1373/20"		

DST 4611-18 op. 1', GTS 30", REC. 180'
 G+MCO + 3470" GASSY OIL (gty 33°)
 FP 218-1290, BHP 1442/20"
 DST 4647-71 op. 1', REC. 8' MUD, FP-45
 BHP 45/20"
 DST 4683-98 op. 1', REC. 90' MUD
 FP 34-48 BHP 1520/20"
 DST 4772-4800 op. 1', REC. 320' GAS +
 1821' OIL (gty 26°), FP 70-532 BHP 1581/20"
 DST 4800-33 op. 1', REC. 60' GAS + 2875'
 GASSY OIL (gty 41°), FP 355-1047, BHP 1080/20"
 DST 4958-5001 op. 1', REC. 2500' xw
 FP 225-1145, BHP 1162/20"
 RTD 5001, logs, VEL. SURVEY, CSG, WOC.
 MICT C.O.

P/32 4804-12, Snd W. + 3 BNO - 1'
 Snd 12' - 119 BNO (9.98 BNO PD) - .87% BS+W
 gty 23.4°

5-27 pump 367.4 BNO - 35'
 pump 10.9 BNO - look h, .17% wtg +
 .1% B.S., W.O.T.

6-3 pump 237 BNO (.27% BS+W) - 22'

pump 1028 BNO - Tot
 481 Bbls allow for Mang
 No Transport Co. hauling

6-11 pump 319 BNO PD, 25.5°
 for 4804-12 clear.

5 JUL 9

Nios 900	ANY 3098	b/KC. 4546
FRAYS 1545	b/Maple Hill 3938	MARM 4559
b/ " " 1604	Tarkis 3946	CHERO 4718
Fairport 1747	Elmont-Reading	MISS 4954
Greenhorn 1833		3967
Jetmore 1848	Howard	4019
Graneros 1927	TOP	4044
Dak. 1983	HP	4229
b/Morrison 2522	TORO	4268
b/Jurassic 2600?	LAN/KC.	4286
Blaine 2726	DRUM	4422