

November, 1934.

Marland #1 Low,
SE SW SW, 30-68-17W,
Elevation 1996'

Pennsylvanian conglomerate. 3460-3493'

3460-3480 Clay shales, dense nodular limes, and rare coarse sand.
3480-3493 Sand, coarse,; with stained chert.

Ordovician Top 3493'

3493-3504 Dolomite, white, fine. Questionably Pre-Cotter. Sub-sea, minus 1497'

There are two other possibilities as to the age of the dolomite: that it is something younger than Arbuckle; and that it may be Willer, the youngest Arbuckle. Neither of these is as convincing as the Pre-Cotter evidence of the lack of chert on or in the dolomite.