

NATIONAL ASSOCIATED PETROLEUM CO.

Office Memorandum

From Joe E. McGarrah Date #1 FAUBION  
To F. H. Lindsay Subject NW SE SW Sec. 1-6S-18W

Rooks Co., Kansas

TYPE: Wildcat  
STATUS: D & A Feb. 26, 1966  
ELEVATION: 1878 Gr., 1880 D.F., 1882 K.B.  
DEPTH: 3440 LANE WELLS, 3442 DRILLER  
DATES: MIRT Feb. 15, 1966, D & A Feb. 25, 1966  
CASING: 250' 8 5/8 set at 254 W/125 sx cement 200# CC 200# AC  
SPECIAL TESTS: Superior Testers, Lane Wells E-log.

DESCRIPTION OF SPECIAL TESTS:

#1 DST 3146-3164 (corrected to E-log 3142-3160) Two zones tested on this test. 3142-3144 - dolomitic white XLN LM with slight show of stain, no odor. 3156-3160 gassy, ool, white, sl-vugular lime with show of brown oil, no saturation, fair odor. This zone calculated too tight for recovery on E-log. Test tool was open for 1/2 hr. S.I. 20", weak blow for 5" then died. Recovered 15' mud. ISIP 880, FSIP 680, IFP 24#, FFP 40#. HH 1666.

FORMATION TOPS:	SAMPLES:	SCHLUMBERGER:
Topeka	2813	2809
Heebner	3017	3013
Toronto	3042	3038
Lan	3059	3054
B/KC	3295	3294
Cong.	3389	3388
Sp. Sd.	3414	3414
Arbuckle	3423	3420
Total Depth	3442	3440

Respectfully Submitted,

Joe E. McGarrah