

34-6-196

# KANSAS DRILLERS LOG


IMPORTANT  
Kans. Geo. Survey request  
samples on this well.  
AUG 8 0 REC'D  
State Geological Survey  
WICHITA, BRANCH

S. 34 T. 6 S R. 19 W

Loc. C NW NE

County \_\_\_\_\_ Rocks \_\_\_\_\_

640 Acres



Elev.: Gr. 2014

DF 2020 KB 2022

API No. 15 — 163 — 21,060  
County Number

Operator  
Cinco Exploration Co.

Address  
3935 Hartsdale Houston, Texas 77063

Well No. #1 Lease Name Odle

Footage Location  
660 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Abercrombie Drilling Co. Geologist Don F. Moore

Spud Date 4-21-80 Total Depth 3603 P.B.T.D.

Date Completed 3360-10 Oil Purchaser

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8	28	261	Class "A"	200	2% gel 3% CA C/2

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

## TUBING RECORD

Size	Setting depth	Packer set at			

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated


## INITIAL PRODUCTION

Date of first production N/A Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-  
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation  
Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody  
is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas  
66044.

Operator <b>CINCO EXPLORATION COMPANY</b>		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDOW, ETC.: <b>Dry Hole</b>	
Well No. <b>1</b>	Lease Name <b>Odle</b>	<b>Plugged 4-28-80</b>	
S <b>34</b> T <b>6s</b> R <b>19</b> <del>EX</del> W			
<b>WELL LOG</b> Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
<b>FORMATION DESCRIPTION, CONTENTS, ETC.</b>	<b>TOP</b>	<b>BOTTOM</b>	<b>NAME</b>
Formation tops			
Formation	Top	Sub-Sea	
Anhydrite	1678	-1444	
Heebner	3217	-1195	
Toronto	3240	-1218	
Lansing	3258	-1236	
Base KC	3464	-1442	
Arbuckle	3567	-1545	
TD	3603	-1581	
DST #1	3310	-3360	
30/30/30/30			
1F 22#/63#			
1S1 1145#			
FF 73#/73#			
FSI 1104#			
Temp 94°			
Recovered 63' of drilling mud with specks of oil Ran petrolog GR DN Guard Log from 3603 to 2900 No show. P/A well 4-28-80			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 <b>MELVIN KLOTZMAN</b> Signature Petroleum Consultant 8-18-80 Date		