

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

1-6-20W

Company - LOUIS R. TRAVIS (Weeder)
Farm - A. H. Cole No. 1

SEC. 1
SW NW SW

T. 6

R. 20W

15-163-00218

Total Depth. 3573

Comm. 6-30-49

Comp. 7-12-49

Shot or Treated.

Contractor. Weeder Supply Co.

Drill. 3-13-49

County.

Rooks

KANSAS



Elevation.

2049 2nd

Production. Dry

CASING:
8 5/8" 250' cem w/150 sx.

Figures Indicate Bottom of Formations.

shale sdy, shells	224
limo sft., chalky	260
shale	575
shale, limo, shells	749
sand, chalky lime	990
shale	1630
anhyd. brkn	1690
shale, anhyd.	1900
shale, sn. redbed	2090
shale, rough sand str	2345
shale, limo sdy.	2610
limo, shells, shale	2760
limo sdy, shale	2850
limo, shale	2910
shale, shells	3045
limo, shale	3135
shale, limo, shells	3220
limo	3480
limo sdy	3525
shale sdy	3536
Regan sand	3560
granite	3573
Total Depth	

Tops:

Topeka	3033
Heebner	3238
Dodge	3254
Lansing	3265
Base K. C.	3432
Regan	3536
G. Wash.	3555