

SEP 13 1969

Sec. 34 - 6S. - 20W
15-103-20175

CONTRACTOR'S WELL LOG



OWNER:
CONTRACTOR:
WELL NAME:
LOCATION:

Rosen Oil Company
Abercrombie Drilling, Inc.
STEELE #1
Appr. 50' East of
C S/2 SW, Sec. 4-6S-20W
Rooks County, Kansas
Burton Schmidt
February 4, 1969
February 12, 1969

GEOLOGIST:
COMMENCED:
COMPLETED:

0	75	Clay & Sand
75	238	Shale
238	800	Shale & Shells
800	1150	Sand
1150	1255	Shale
1255	1450	Sand
1450	1755	Red Shale
1755	1780	Anhydrite
1780	2110	Shale
2110	2340	Shale & Lime
2340	2940	Lime & Shale
2940	3115	Lime
3115	3390	Lime & Shale
3390	3610	Lime
3610	3622	Sand
	3622	Rotary Total Depth

oil

Drilled 230' of 11" surface hole and set 7-5/8" csg. @226' w/135 sx. GL-3 cement.
Cement circulated. Plug was down at 1:00 a.m., 2-4-69.
Casing was set at 2:00 a.m., 2-12-69.

ELEVATION:

2147 K. B.
2141 D. F.
2139 G. L.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

A. L. Abercrombie, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the STEELE #1, 50' E/L of the C S/2 SW, Sec. 4-6S-20W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

[Signature]
A. L. Abercrombie