

15-163-01108

DERBY OIL CO.-CROW DRILLING CO.
 Steele No. 1


SEC 9 T. 6 R. 20 W.
 CN $\frac{1}{2}$ NW NW

DISCOVERY WELL

57979

County Rocks.

Total Depth. 3639
 Comm. 12-1-41 Comp. 1-1-42
 Shot or Treated.
 Contractor. Crow Drilling Co.
 Issued. 3-21-42



CASING.

85/8" 161' cemented.
 4 $\frac{1}{2}$ " 3602' cemented.

Elevation.

Production. Pot. 183 B.

Figures Indicate Bottom of Formations. No wtr. Pump.

sand	63
shale and shells	105
shale	138
shale and shells	155
shale	1834
shale and shells	1103
shale	1172
lime	1196
shale and lime	1250
shale	1269
sand	1447
red rock shale and shells	1620
shale	1719
sand	1759
broken lime	1831
shale	1856
red bed	1877
shale and shells	2022
shale	2160
broken lime	2185
shale and lime strks	2225
shale	2359
lime	2372
shale	2409
lime	2428
shale & lime strks	2480
shale	2590
lime	2606
shale	2609
shale and limo	2644
shale	2661
lime	2707
shale	2721
shale and lime	2825
shale	2847
lime	2863
shale	2882
shale and lime	2922
shale	2972
shale and lime	2992
lime	3014
shale and lime	3034
lime	3045
shale	3055
lime	3077

shale	3086
limo and shale strks	3147
lime	3200
cherty limo	3218
lime	3405
lime & strks of Sh.	3430
limo	3498
lime and chort	3521
limo	3569
shale	3600
lime	3625
sand	3628
granite	3639
Total Depth.	

D.P. 3639 T.D. Hole caved
 C.O. and Sub. 28.14 oil in 4
 hours. 25' of cavings back in
 hole - clean out and sub. 6 $\frac{1}{2}$
 oil per hr for 2 hours. Hole
 caved in again - cleaned out
 Run rods and tubing.
 Pump Potential 183 bbls oil no
 water.

TOPS-
 Lansing 3359
 Arkosic sand 3613
 Granite Wash 3636
 Solid Granito 3638