

15-065-00054

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


61174

Company - TEXAS CO.
Farm - ~~L. Voss~~
 VOSS
No. 1.

SEC. 9 T. 6 R. 21 W
SWc SW

Total Depth. 3825(Drlrs) 3832(Schlum)
Comm. 8-4-44 Comp. 8-22-44
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 9-30-44

County. Graham
KANSAS



CASING:
8 5/8" 1907' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shells	30
sand	130
sand & gravel	180
shale & shells	775
shale	965
shale & shells	1155
shale & sand	1275
shale & chert →	1300
shale & shells	1340
shale & sand	1370
shale & shells	1430
sand	1600
shale & sand	1650
shale	1665
shale & shells	1685
red bed & shale	1715
red bed	1815
red bed & shale	1898
anhydrite	1960
red bed	2100
shale & shells	2528
lime & shale	2630
shale & shells	2775
lime & shale	2970
lime	3010
lime & shale	3410
K C lime	3420
lime	3520
lime & chert →	3596
lime	3696
lime sft	3714
lime & shale	3790
lime	3800
lime Arbuckle	3825
Total Depth (Drlrs)	
TD(Schlumberger)	3832

Tops:

Anhydrite	1898
K.C. lime	3460
Cored	3758-64
4" rec.	
Cored	3786-90
3" lime rec.	
Arbuckle lime	3787