

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Trexler "B" No. 1

SEC. 36 T. 6 R. 23W
 C SE SE

Total Depth. 3803'
 Comm. 2-23-59 Comp. 3-5-59
 Shot or Treated.
 Contractor. Imperial Oil
 Issued. 6-27-59

County Graham
 KANSAS



Elevation. 2361' RB

Production. 108 BOPD & 61% Wtr.

CASING:

8 5/8" 216' cem w/165 sx.
 5 1/2" 3803' cem w/125 sx.

Figures Indicate Bottom of Formations.

sand & shale 216
 shale & shells 1440
 sand-shale & shells 2014
 Anhydrite 2050
 shale & shells 2325
 shale & lime 3620
 lime 3803 RTD
 Total Depth

TOPS:	SAMPLE	ELECTRIC
Anhydrite	2014	
Heebner	3572	3570
Toronto	3596	3594
Lansing	3612	3610

DST #1 3606-20, op 1 hr, rec. 250'
 slightly oil cut salt water, 90' heavy
 oil cut salt water, 90' very slight oil
 cut salt water, 120' salt water, BHP
 1325#.

DST #2 3636-52', op 1 hr, rec. 1000'
 gas, 1120' oil, BHP 1310#.

DST #3 3651-68', op 1 hr., rec. 20'
 mud, BHP 1190#.

DST #4 3669-79, op 1 hr, rec. 10' mud,
 BHP 0#.

DST #5 3678-88, op 1 hr, rec. 30' mud
 w/specks oil, BHP 860#.

DST #6 3718-48', op 1 hr., rec. 10'
 mud, BHP 480#.

DST #7 3745-59', op 1 hr., rec. 10' mud,
 BHP 30#.

DST #8 3758-78', op 1 hr., rec. 15'
 mud, BHP 15#.