

KANSAS DRILLERS LOG

15-065 21136

30-6-25W


API No. 15 — 065 — 21136
 County Number

S. 30 T. 6S R. 25W E
 W

Loc. NW NE SW

County Graham

640 Acres
 N



Elev.: Gr. 2623

DF 2629 KB 2631

Operator
Beren Corporation

Address
970 Fourth Financial Center, Wichita, Kansas 67202

Well No. 1 Lease Name ROBERTS

Footage Location
 feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Abercrombie Drilling, Inc. Geologist Kent Crisler

Spud Date September 20, 1979 Total Depth 3950 P.B.T.D. _____

Date Completed September 27, 1979 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4	8-5/8	28#	330'	60-40 pozmix	225	2% gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Beren Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name ROBERTS

Dry hole

S 30 T 6 R 25^E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay, sand and shale	0	331		
Shale	331	1242		
Shale and sand	1242	2216		
Anhydrite	2216	2249		
Shale	2249	2370		
Lime and shale	2370	2820		
Shale and lime	2820	3055		
Lime and shale	3055	3808		
Lime	3808	3835		
Lime and shale	3835	3950		
Rotary Total Depth	3950			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Don Beauchamp
Signature

Don Beauchamp - Geologist
Title

October 4, 1979
Date

20-6-320

CONTRACTOR'S WELL LOG

OPERATOR: Beren Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Roberts #1
 LOCATION: NW NE SW, Section 30-6S-25W
 Graham County, Kansas
 SPUD DATE: September 20, 1979
 COMPLETION DATE: September 27, 1979

0	331	Clay, sand and shale
331	1242	Shale
1242	2216	Shale and sand
2216	2249	Anhydrite
2249	2370	Shale
2370	2820	Lime and shale
2820	3055	Shale and lime
3055	3808	Lime and shale
3808	3835	Lime
3835	3950	Lime and shale
	3950	Rotary Total Depth

Spud hole at 1:00 p.m., September 20, 1979. Drilled 331' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 28# used casing. Set at 330' with 225 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 6:15 p.m., September 20, 1979.

T.D. 3950'. Set 1st plug at 1320' with 60 sacks, 2nd plug at 330' with 30 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 10:00 a.m., September 27, 1979.

SAMPLE TOPS:

Anhydrite 2216'
 B/Anhydrite 2249'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Roberts #1, NW NE SW, Section 30-6S-25W, Graham County, Kansas.