

15-065-30348  
31-6-25W

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY OKMAR OIL CO.

SEC. 31 T. 6 R. 25W  
LOC. CS/2 NW NW

FARM Brewster

NO. 1

TOTAL DEPTH 3900'

COMM. 12-11-67

COMP. 12-19-67


SHOT OR TREATED

CONTRACTOR Leben Drlg, Inc.

ISSUED 1-13-68

COUNTY Graham

KANSAS



CASING

|    |       |                    |
|----|-------|--------------------|
| 20 | 10    |                    |
| 15 | 8 5/8 | 325' w/225 sx cem. |
| 12 | 6     |                    |
| 13 | 5     |                    |

ELEVATION 2606' KB

PRODUCTION DRY (LKC)

FIGURES INDICATE BOTTOM OF FORMATIONS

|      |             |               |             |        |
|------|-------------|---------------|-------------|--------|
| 0    | 100         | Clay, Sand    | TOPS: SCOUT | SAMPLE |
| 100  | 325         | Sand, Shale   | Anhydrite   | 2196   |
| 325  | 685         | Shale         | B/Anhydrite | 2230   |
| 685  | 1585        | Shale, Sand   | Heebner     | 3679   |
| 1585 | 1600        | Sand          | Toronto     | 3703   |
| 1600 | 2196        | Sand, Shale   | Lansing     | 3717   |
| 2196 | 2230        | Anhydrite     |             |        |
| 2230 | 2320        | Shale         |             |        |
| 2320 | 2614        | Lime, Shale   |             |        |
| 2614 | 3080        | Shale, Lime   |             |        |
| 3080 | 3620        | Lime, Shale   |             |        |
| 3620 | 3900        | Lime          |             |        |
|      | <u>3900</u> | RTD - D. & A. |             |        |



8 5/8" 8 rd. 24# used surface casing set @ 325' cemented with 225 sacks Common, 7% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Brewster #1 Well, located S 1/2 NW NW of Section 31, Township 6 South, Range 25 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
COUNTY OF BARTON ) SS

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 20th day of December, 1967.

*Glenda Nichols*

Glenda Nichols