

15-005-30182
31-6-25W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY OKMAR OIL CO.

SEC. 31 T. 6 R. 25W
LOC. CS/2 SW NW

FARM Lindeman

NO. 1

TOTAL DEPTH 3890'

COMM. 11-30-65

COMP. 12-8-65


SHOT OR TREATED

CONTRACTOR Leben Drlg., Inc.

ISSUED 5-14-66

COUNTY Graham

KANSAS



CASING

20	10	
15	8 5/8	265' w/200 sx cem.
12	6	
13	5	3890'

ELEVATION 2589' K.B.

PRODUCTION Pmp. 64 BOPD
NW

FIGURES INDICATE BOTTOM OF FORMATIONS

0	90	Clay, Sand	TOPS: SCOUT	
90	220	Shale, Sand	* Anhydrite	2172
220	1130	Shale	Topeka	3492
1130	1245	Sand, Shale	Heabner	3648
1245	1375	Shale, Sand	Toronto	3670
1375	1550	Sand	Lansing	3686
1550	1860	Shale, Redbed	B/Kansas City	3883
1860	2172	Shale, Shells	* Sample tops.	
2172	2206	Anhydrite		
2206	2590	Shale, Shells		
2590	3225	Lime, Shale		
3225	3390	Lime		
3390	3530	Shale, Lime		
3530	3650	Lime, Shale		
3650	3890	Lime		
	3890	RTD - Set 5 1/2" Casing		

Set 8 5/8" used surface casing w 265' cemented with 200 sacks Sunset 2% Gel

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lindeman #1 well, located South Half SW NW of Section 31, Township 6 South, Range 25 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite