

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


31-6-25W

Company- PEEL-HARDMAN OIL  
Farm- Linderman No. 1

SEC. 31 T. 6 R. 25W  
SE SE SE

Total Depth. 3845'  
Comm. 6-20-59 Comp. 7-3-59  
Shot or Treated.  
Contractor. Glenn W. Peel Drlg.  
Issued. 8-22-59

County Graham  
KANSAS



Elevation. 2567' RB

Production. 340 BOPD

CASING:

8 5/8" 285' cem.  
5 1/2" 3841 1/2' cem.

Figures indicate Bottom of Formations.

surface clay	30
sand	255
shale	1000
sand & shale	1410
shale	1470
sand	1530
shale	1545
shale & sand	1800
shale	1945
red bed	2090
shale	2155
Anhydrite	2190
shale	2850
lime & shale	3110
shale	3200
lime & shale	3380
shale	3510
lime & shale	3680
lime	3845
Total Depth	

TOPS: K.B.

Anhydrite	2155
Heebner	3635
Toronto	3654
Lansing	3672