


7-6-26w

Company- IMPERIAL OIL of KANSAS, INC.
 Farm- Randolph No. 1

SEC. 7 T. 6 R. 26W
 SW SW SW

Total Depth. 3934'
 Comm. 12-19-55 Comp. 1-13-56
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 7-28-56

County Sheridan
 KANSAS



CASING:

Elevation. 2575' RB

8 5/8" 322' w/225 sx cem.

Production. 82 EOPD

Figures indicate Bottom of Formations.

shale-shells	140
sand	190
shale-shells	2100
red bed shale-shells	2195
Anhydrite	2225
shale-shells	2790
shale-lime	3625
lime	3934
Total Depth	

TOPS:	DRILLER	HALLIBURTON
Anhydrite	2123	(Corr)
Heebner	3569	3554
Lansing	3611	3594
B/Kansas City	3810	3796

- DST #1-3631-54 Open 1 hr., rec. 30' oil, 115' HOCM. FP 35#-70# EHP 575#.
- DST #2-3677-94 Open 2 hrs., rec. 120' gas, 50' OCM, 50' HOCM. FP 35#-70# EHP 240#.
- BST #3-3696-3712 Open 4/5 min. Rec. 55' mud. No oil. EHP 575#. The 100' zone judged unworthy of further testing.
- DST #4-3719-40 Open 1/2 hr. Rec. 15' mud w/trace oil, EHP 100#. The 140' zone judged unworthy of further testing.
- DST #5-3768-90 Open 1/2 hr. Rec. 6' mud. EHP 70#. Because of the show of oil & the offsetting well producing from this zone, the 200' zone is judged worthy of further testing.

An error in the frilling measurements of approximately 15' was detected upon reaching the total depth. Sample tops and DST's as reported should be moved up the hole 15' to match the Halliburton log.