

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


17-6-26W

Company: IMPERIAL OIL OF KANSAS, INC.
Farm: Shipley No. 1

SEC. 17 T. 6 R. 26W
SE SE SW

Total Depth. 3927
Comm. 7-29-55 Comp. 8-7-55
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 10-22-55

County Sheridan
KANSAS



8 5/8 @ CASING: 318' w/ 2 1/2" sx cmt.
5 1/2 @ 3909' cmtd.

Elevation. 2649 RB

Production. 400 BOPD (Private test)

Figures indicate Bottom of Formations.

shale, sand & shells	318
clay, sand, shale & shells	815
shale & shells	1250
sand & shale	1810
Dakota sand	2030
shale & shells	2055
shale, shells & red bed	2245
anhydrite	2285
shale & shells	2796
shale & lime	3375
lime	3909
lime	3927
Total Depth	

TOPS:

Anhydrite	2245
Heebner	3698
Toronto	3722
Lansing	3740

DST #1: 3706-33, open 30 min. rec.
10' mud, IFP & FFP O#, BHP 720#/20 min.

DST #2: 3755-77, open 30 min. rec.
10' mud, BHP O#

DST #3: 3774-95, open 35 min. rec.
20' mud, IFP & FFP O#, BHP 1015#/20 min.

DST #4: 3802-16, open 1 hr. rec. 1920'
gas 60' muddy oil, 180' free oil,
IFP O#, FFP 110#, BHP 1150#/20 min.

DST #5: 3818-32, open 1 hr. rec. 10'
mud. BHP 270#/20 min.

DST #6: 3834-48, open 1 hr. rec. 52'
muddy water, IFP O#, FFP 25#, BHP
700#/20 min.