

KANSAS DRILLERS LOG


17-6-26W

API No. 15 — 179 — 20,553
County Number

S. 17 T. 6S R. 26 E
Loc. App. SE SW SW

County Sheridan

640 Acres
N



Locate well correctly

Elev.: Gr. 2655'

DF KB 2660'

Operator A. Scott Ritchie	
Address Suite 950 - 125 N. Market; Wichita, Ks. 67202	
Well No. 2	Lease Name Shipley
Footage Location 330 feet from (N) (S) line 990 feet from (E) (W) line of SW/4	
Principal Contractor Murfin Drilling Co.	Geologist Greg Cheney
Spud Date 2/16/80	Total Depth 3955'
Date Completed 2/23/80	P.B.T.D.
Oil Purchaser none	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/4"	8 5/8"	28#	404'	60-40 pozmix	300	3% cc; 2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator A. Scott Ritchie		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole	
Well No. 2	Lease Name Shipley		
S17 T 6S R 26 X W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
DST #1 3710'-3779' Rec. 10' mud. IFP 64-64#/30"; ISIP 309#/30"; FFP 64-64#/30"; FSIP 299#/30"			
DST #2 3778'-3804' Rec. 5' mud. IFP 21-21#/30"; ISIP 43#/30"; FFP 21-21#/30"; FSIP 32#/30".			
DST #3 3796'-3820' Rec. 10' mud with specks of oil. IFP 43-43#/30"; ISIP 181#/30"; FFP 43-43#/30"; FSIP 138#/30".			
DST #4 3817'-3836' Rec. 2' mud. IFP 32-32#/30"; ISIP 32#/30"; FFP 32-32#/30"; FSIP 32#/30".			
DST #5 3839'-3900' Rec. 10' oil specked mud. IFP 53-53#/30"; ISIP 309#/30"; FFP 53-53#/30"; FSIP 287#/30".			
DST #6 3896'-3955' Rec. 10' mud with scum of oil. IFP 32-32#/30"; ISIP 938#/30"; FFP 43-43#/30"; FSIP 810#/30".			
			SAMPLE TOPS
			Anh 2255' (+ 405)
			B/Anh 2287' (+ 373)
			Top 3502' (- 842)
			Heeb 3704' (-1044)
			Toro 3727' (-1067)
			Lans 3743' (-1083)
			B/Kc 3943' (-1283)
			RTD 3955' (-1295)
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Geologist Title March 4, 1980 Date		