

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


18-6-26W

Company- IMPERIAL OIL CO.
Farm- Hardesty No. 1

SEC. 18 T. 6 R. 26W
SE SE SW

Total Depth. 3940'
Comm. 10-11-61 Comp. 10-20-61
Operator Treated.
Contractor. Imperial Oil Co.
Issued. 1-6-62

County Sheridan
KANSAS



CASING:
7" 338' cem w/200 sx.

Elevation. 2678' KB

Production. Dry

Figures indicate Bottom of Formations.

shale & sand	285
shale	680
sand & shale	1220
shale	1402
sand & shale	1650
shale	1883
red bed	2064
red bed & shale	2260
Anhydrite	2293
shale	2475
shale & shells	2768
lime & shale	3090
lime	3940 RTD
Total Depth	

TOPS:
Anhydrite (scout) 2260
Base Anhydrite (scout) 2293
Heebner 3693
Toronto 3717
Lansing 3735
Base Kansas City 3935

DST #1 3746-88', op 45 mins, rec. 5'
drilling mud. IBHP 178#, IFP 0#, FFP 0#,
FBHP 60#/30 mins.

DST #2 3736-3839', op 30 mins, rec. 5'
drilling mud. IBHP 570#, IFP 0#, FFP 0#,
FBHP 435#/20 mins.

DST #3 3858-3940', op 30 mins, rec. 10'
mud, IBHP 1085#, IFP 0#, FFP 0#, FBHP 955#/
20 mins.