

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


18-6-26W

Company- IMPERIAL OIL OF KANSAS, INC.  
Farm- Muir "A" No. 3

SEC. 18 T. 6 R. 26W  
SW NW NW

Total Depth. 3810'  
Comm. 3-9-58 Comp. 3-19-58  
Shot or Treated.  
Contractor. Imperial Oil of Kansas, Inc.  
Issued. 6-28-57

County Sheridan  
KANSAS



CASING:  
8 5/8" 189' cem w/150 sx.  
5 1/2" 3810'

Elevation. 2610' RB

Production. 170 BOPD, no Wtr.

Figures Indicate Bottom of Formations.

surface sand	190
shale & sand	1265
hard sand & pyrite	1450
Dakota sand	1600
shells & shale "hard"	2146
Anhydrite	2185
shale & shells	2300
shale	2680
shale & shells	2910
shale & lime	3465
lime	3810 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC LOG
Anhydrite	2146	2152
Heebner	3574	3574
Toronto	3597	3597
Lansing	3616	3614

DST #1 3632-56, op 20 mins, rec. 500' gas  
125' heavily oil cut mud, 125' very  
heavily oil cut mud, BHP 470#.