

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

21-6-26W

COMPANY **HALLIBURTON OIL PRODUCTION**

SEC. 21 T. 6 R. 26W

FARM **Wente** NO. **1**

LOC. **SE SE NE**

TOTAL DEPTH **3925**

COUNTY **Sheridan**


COMM. **1-8-67**

COMP. **1-17-67**

SHOT OR TREATED

CONTRACTOR **Empire Drlg.**

ISSUED **4-22-67**



CASING

20	10	
15	8	5/8" @ 321' w/175 sx
12	6	
13	4 1/2"	@ 3925' w/185 sx

ELEVATION **2617' KB**

PRODUCTION **PMP 6 BOPD & 47 BW/LANS KC 3757-61**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	340	Surface-Shale
340	to	1320	Shale & Bentonite
1320	to	1682	Shale & Sand
1682	to	1835	Shale & Gypsum
1835	to	2010	Sand
2010	to	2232	Shale
2234	to	2267	Anhydrite
2267	to	2620	Shale
2620	to	3120	Lime & Shale
3120	to	3505	Lime
3505	to	3616	Lime & Shale
3616	to	3925	Lime
3925			Rotary Total Depth

SET: 321' of 8 5/8" with 175 sacks cement.
 3925' of 4 1/2" with 185 sacks cement.

ELECTRIC LOG TOPS:

Anhydrite	2230	+387
Base Anhydrite	2264	+353
Heebner	3693	-1076
Lansing	3731	-1114
Total Depth	3925	

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on Wente #1, SE SE NE Section 21-6-26W, Sheridan County, Kansas, as reflected by the files of Empire Drilling Company.

 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 26th day of January, 1967.