

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

23-6-26W

COMPANY A. L. ABERCROMBIE INC.  
 FARM Allen NO. 1

SEC. 23 T. 6 R. 26W  
 LOC. App C W 1/2 SW NE

TOTAL DEPTH 3855'  
 COMM. 12-8-67 COMP. 1-25-68  
 SHOT OR TREATED  
 CONTRACTOR Abercrombie Drlg.  
 ISSUED 2-~~12~~-68  
 3.4

COUNTY Sheridan  
 KANSAS


CASING  
 20 10  
 15 ~~X~~ 7 5/8" 315' cem w/ 150 sx  
 12 6  
 13 5  
 4 1/2" 3854' cem w/ 100 sx

ELEVATION 2562' KB

PRODUCTION 288 BOP  
 Grav 39.6/ Lens 37

FIGURES INDICATE BOTTOM OF FORMATIONS

0	230	Sand & Clay
230	280	Clay
280	320	Shale
320	1045	Shale & Shells
1045	1163	Sand
1163	1725	Shale w/Sand Streaks
1725	1741	Shale
1741	1918	Sand
1918	2149	Red Bed & Shale
2149	2181	Anhydrite
2181	3155	Shale & Lime
3155	3616	Lime & Shale
3616	3720	Lime
3720	3795	Lime & Shale
3795	3840	Lime
3840	3855	Shale
	3855	Rotary Total Depth

Set 7-5/8" casing @315' w/150 sx. Sunset cement. Plug was down 2:30 a.m., 12-8-67.  
 Set 4-1/2" casing @3854' w/100 sx. salt-saturated cement. Plug was down 6:00 a.m., 12-17-67.

ELECTRIC LOG TOPS

ELEVATION

Anhydrite	2142	(+ 420)	2562	K. B.
Heebner	3602	(-1040)	2561	D. F.
Toronto	3623	(-1061)	2555	G. L.
Lansing	3639	(-1077)		
B/Kansas City	3637	(-1275)		
E.L.T.D.	3840	(-1278)		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, A. L. Abercrombie, President of Abercrombie Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 ALLEN, 220' West of SW/4 NE/4 of Section 23-6S-26W, Sheridan County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

*A. L. Abercrombie*