

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

23-6-26W

COMPANY ABERCROMBIE DRILLING

SEC. 23 T. 6 R. 26W

FARM Brandt

NO. 1

LOC. C SE NW

200' E of

TOTAL DEPTH 3855'

COMM. 9-14-67

COMP. 9-22-67


SHOT OR TREATED

CONTRACTOR Abercrombie Drlg

ISSUED 11-18-67

COUNTY Sheridan

KANSAS



CASING

20

10

15

8

5/8" 294' cem w/ 135 sx

12

6

13

5

4 1/2" 3864.5' cem w/ 150 sx

FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 2557' KB

PRODUCTION 281 BOPD, NW/

Lans 3805-08 Gray 39

0	66	Gravel
66	211	Sand
211	1520	Shale
1520	1741	Shale w/Sand Streaks
1741	1919	Sand
1919	2143	Red Bed Shale
2143	2177	Anhydrite
2177	2325	Shale
2325	2685	Shale w/ Gyp. Streaks
2685	3100	Shale & Lime
3100	3205	Lime & Shale
3205	3405	Shale & Lime
3405	3650	Lime & Shale
3650	3828	Lime
3828	3855	Lime & Shale
	3855	Rotary Total Depth

Set @ 294, 7 inch casing with 135 sacks of cement.

Set 4-1/2" casing @3854.5 with 150 sacks of common cement.

ELECTRIC LOG TOPS:

ELEVATION: 2557 K.B.
 2556 D.F.
 2550 G.L.

Anhydrite	2143	(+ 414)
Heebner	3602	(-1045)
Toronto	3624	(-1067)
Lansing	3640	(-1083)
B/K.C.	3838	(-1281)
Total Depth	3856	(-1299)

TOPS: SMP

Anhydrite	2143
Base Anhydrite	2177
Heebner	3600
Toronto	3620
Lansing	3636