TYPE

AFFIDAVIT OF COMPLETION FORM X ACO-1 WELL HISTORY

26-6-26W

SIDE ONE

(Rules 82-3-130 and 82-3-107) DOCKET NO. NP

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F ____ Letter requesting confidentiality attached.

C XX Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run ____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5342 EXPIRATION DATE June

OPERATOR Beacon Exploration Company API NO. 15-179-20,767

ADDRESS 410 17th St., Suite 2300 COUNTY Sheridan

Denver, Colorado 80202 FIELD Wildcat

** CONTACT PERSON David Kranz PROD. FORMATION N/A

PHONE (303) 825-1966 ____ Indicate if new pay.

PURCHASER N/A LEASE Teel

ADDRESS ____ WELL NO. 1-26

WELL LOCATION C/NE SW NW

DRILLING CONTRACTOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300

Wichita, Kansas 67202

990 Ft. from W Line and

1650 Ft. from N Line of


the NW (Qtr.) SEC 26 TWP 6S RGE 26 (W).

PLUGGING CONTRACTOR Leo Swords

ADDRESS Box 288

Russell, Kansas 67665

WELL PLAT



(Office Use Only)

KCC ✓

KGS ____

SWD/REP ____

PLG. ____

NGPA ____

TOTAL DEPTH 4050' PBTD --

SPUD DATE 10/18/84 DATE COMPLETED 10/26/84

ELEV: GR 2625' DF -- KB 2630'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE N/A.

Amount of surface pipe set and cemented 384' DV Tool Used? No.

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion --. Other completion --. NGPA filing --.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

David Kranz, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

ACO-1 Well History

Side TWO

OPERATOR Beacon Exploration Co. LEASE NAME Teel SEC 26 TWP 6S RGE 26 (W)

WELL NO 1-26

FILL IN WELL INFORMATION AS REQUIRED;

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
_____ Check if no Drill Stem Tests Run. _____ Check if samples sent Geological Survey. Kansas City 'B-C' DST #1: 3776-3816' 15-30-60-120 IH 2000 FH 1948 ISIP 1125 FSIP 1053 IFP 132-357 FFP 438-684 BHT 108° F Rec. 1350' GCMW Kansas City 'G' DST #2: 3814-54' 25-30-60-120 IH 1876 FH 1825 ISIP 991 FSIP 1022 IFP 91-163 FFP 234-367 BHT 109° F Rec. 735' GCMW (40% M; 60% W), oil spotted TD		4050'		

RECEIVED
NOV 2 8 1984

If additional space is needed use Page 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	384'	60/40 Poz	260	2% Gel, 3% $CaCl_2$

LINER RECORD N/A

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD N/A

Size	Setting depth	Packer set at

PERFORATION RECORD N/A

Shots per ft.	Size & type	Depth interval

WELL LOG

26-6-26W

COMPANY Beacon Exploration Company
419 17th St., Suite 2300
Denver, Colorado 80202


SEC. 26 T. 6S R. 26W
LOC. NE SW NW

FARM TEEL NO. 1-26

RIG. NO. 3

TOTAL DEPTH 4050'

COUNTY Sheridan
KANSAS



COMM. 10-18-84 COMP. 10-26-84

CONTRACTOR MURFIN DRILLING COMPANY
250 N. Water, Suite 300
Wichita, Kansas 67202

CASING

20 10
15 8 -5/8" csg. set @ 384' w/260 sx. 60-40 Pozmix ELEVATION
12 6 2% Gel, 3% CC
13 5 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay & Sand	275'
Shale	450'
Sand & Shale	2240'
Anhydrite	2273'
Sand & Shale	3400'
Lime & Shale (RTD)	4050'

KANSAS