

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

36-6-26W

COMPANY **OKMAR OIL**

SEC. 36 6 N. 26W
 LOC. NE NW SE

FARM **Wente**

NO. 1

15-179-20007

TOTAL DEPTH **3890'**

COMM. **4-18-67**


COMP. **4-25-67**

COUNTY **Sheridan**
 KANSAS

SHOT OR TREATED

CONTRACTOR **Leben Drlg.**

ISSUED **5-27-67**



CASING

20	10	
15	8	5/8" 274' cem w/200 sx
12	6	
13	5	

ELEVATION **2591' KB**

PRODUCTION **Dry/ Lans**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	70	Clay, Sand	
70	274	Sand, Shale	
274	1000	Shale	
1000	1375	Shale, Sand	
1375	1570	Shale, Shells	
1570	2090	Shale, Shells, Redbed	
2090	2179	Redbed	
2179	2221	Anhydrite	
2221	2430	Redbed, Shale	TOPS: SCOUT
2430	2730	Shale	Anhydrite 2179
2730	2925	Shale, Lime	Base Anhydrite 2221
2925	3716	Lime, Shale	Heebner 3658
3716	3890	Lime	Toronto 3690
	<u>3890</u>	<u>RTD - D. & A.</u>	Lansing 3705

8 5/8" 24# used surface casing set @ 274' cemented with 200 sacks
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Wente #1 Well, located
 NE NW SE of Section 36, Township 6 South, Range 26 West, Sheridan
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 26th day of April, 1967.