

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-179-07302


1-6-27W

Company - CONTINENTAL OIL CO.
Farm - C. Cramer "A" No. 1

SEC. 1 T. 6 R. 27 W
SW₆ SW
330' N & 330' E of SW cor.

Total Depth. 3809'
Comm. 2-18-45 Comp. 3-23-45
Shot or Treated.
Contractor.
Issued. 7-14-45

County. Sheridan
KANSAS



CASING:
10 3/4" 240' Cem.
6" 3808' Cem.

Elevation. 2579

Production. Phy. Pot. 498 BO
pump.

Figures Indicate Bottom of Formations.

shale & shells	0-79
sand & shale	250
shale & shells	409
shale	1112
shale & shells	1208
shale & sand shells	1345
shale & shells	1512
shells & sdy shale	1594
shale & shells	2676
shale	2712
shale & shells	2972
lime	3756
lime brkn	3809
Total Depth.	

Top of Lansing lime 3585'

3-31-45 - Drilled cement to 3777'

4-5-45 - Ran Lane-Wells combination radioactivity log & perf. csg. w/Lane-Wells gun as follows; 3790'-3797' w/24 shots - bailed 5 gals. drilling wtr & mud - no show of oil; 3770'-85' w/38 shots - bailed 10 gals of drlg. wtr. - no show of oil; 3750-60' w/21 shots - no show of oil or wtr; 3683-90' w/21 shots - hole filled 2100' w/wtr in 1 hr. & 40 min.

4-8-45 - dumped 6 sacks of cement on top of bridge set @ 3710' to shut off wtr; top of cement 3660'.

4-12-45 - Drilled out cement bridge to 3668'. Perforated csg. from 3650-66' w/21 shots - hole filled 1330' w/wtr in 1 1/2 hrs; 3617'-24' w/21 shots - no inc. in fillup; 3580-95' w/42 shots - hole filled up 800' w/oil & 2500' w/wtr.

4-17-45 - Dumped 6 sacks of cement to plug off perf. from 2650-66'; top of cement 3626'.

4-22-45 - Swbd 100 BO in 5 hrs. off btm.

4-23-45 - Established temporary potential by swbg 60 BO in 3 hrs.

5-24-45 - Established a 24 hr. phy.