

15-179-05287


2-6-27w

Company - CONTINENTAL OIL CO.  
Farm - A.M. Bouts No. 3.

SEC. 2 T. 6 R. 27 W  
NW SE SW  
990' N 990' W S $\frac{1}{4}$  Cor.

Total Depth. 4092' PB 3771'  
Comm. 8-11-44 Comp. 9-30-44  
Shot or Treated.  
Contractor.  
Issued. 11-25-44

County. Sheridan  
KANSAS



Elevation. 2619

Production. Phy. Pot. 430 B.Pmp

CASING:  
10 $\frac{3}{4}$ " 241' Cem.  
6" 3802' Cem.

Figures Indicate Bottom of Formations.

- shale & shells 0-100
- sand hd 120
- shale & shells 1165
- lime brkn 1647
- shale 1980
- shale & shells 2161
- lime 2202
- lime brkn 2362
- lime 2442
- lime brkn 2542
- shale 2636
- lime 2690
- lime brkn 2747
- lime 2787
- lime brkn 2865
- lime 3872
- lime brkn 3889
- lime 4047
- lime & shale 4067
- shale 4090
- granite hd 4092
- Total Depth

P.B. 3771

Top of KC Lime 3610

- 9-19-44 Plug stopped 3771';  
ran Lane-Wells Radioactivity  
log; perforated 6"OD csg w/  
Lane-Wells gun perf 3752-64  
w/48 shots; swabbed 178 BO  
in 4 hrs off btm
- 9-23-44 Perf 6"OD csg w/Lane-  
Wells gun perf 3733-39 w/48  
shots; no inc in oil
- 9-27-44 Ripped 6"OD csg  
3615-23; swabbed 294 BO in  
6 hrs off btm
- 10-2-44 Established a 24 hr  
phy pot of 430 BO, by pmp

PBTD 3771 in KC Lime

Note: Footages calculated from