

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-179-05285


2-6-27W

Company - CONTINENTAL OIL CO.
Farm - A.M. Bouts No. 5.

SEC. 2 T. 6 R. 27 W
NEc SW
330' S & 330' W of the Center

Total Depth. 3840
Comm. 1-18-45 Comp. 2-11-45
Shot or Treated.
Contractor.
Issued. 5-12-45

County. Sheridan
KANSAS



CASING:
10 3/4"
6"
237' Cem.
3837' Cem.

Elevation. 2602

Production. Phy. Pot. 1162 B.

Figures Indicate Bottom of Formations.

sand & gravel	0-145
shale & shells	250
shale	750
shale & shells	1320
sand	1361
lime brkn	1723
shale & shells	2189
lime brkn	2638
lime	2756
shale	2882
lime brkn	2951
lime hrd	2988
lime	3610
shale	3627
lime brkn	3660
shale	3695
lime	3746
shale	3840
Total Depth	

Top of Lansing Lime 3574

3-2-45 Drilled out cement to 3819; ran Radioactivity log; perf 6"OD csg as follows: 3805-16 w/33 shots - small show of oil, 3783-3804 w/72 shots - small show of oil, 3763-74 w/36 shots - small show of oil, 3747-51 w/ 24 shots - small show of oil, and 3705-16 w/ 9 shots - hole filled 600' w/oil in 1/2 hr.

3-6-45 Swbd 33 BOPH for 3 hrs off bottom.

3-8-45 Perf 6"OD csg from 3703-16 w/36 shots and from 3571-99 w/17 shots; have 3500' of oil in the hole; swbd 67 BOPH for 4 hrs at 1100' off bottom.

5-23-45 Established a 24 hr Phy. Pot of 1162 BO.

T.D. in Lansing Lime 3839
(Top of cement 3819)

Note: Footages are calculated from DF level, except formations. It is 2 1/2' from DF to ground level.