

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-179-05292
2-6-27W

Company - CONTINENTAL OIL CO.
Farm - B.H. Boutz No. 1.

SEC. 2 T. 6 R. 27 W
NE SE NW
990' N & 330' W of Cen. of Sec.

Total Depth. 3793
Comm. 6-9-45 Comp. 6-28-45
Shot or Treated.
Contractor.
Issued. 9-15-45

County. Sheridan
KANSAS



CASING:
10 3/4" 240' Cem.
6" 3792' Cem.

Elevation. 2543 ft

Production. Pot. 800 B

Figures Indicate Bottom of Formations.

surface clay, sand & gravel	0-115
sand & shale	250
shale	258
shale & shells	1155
shale sdy	1298
shale sdy & shells	1530
shale	1554
shale & shells	2623
shale	2641
shale & shells	2696
lime brkn	2856
lime	3747
lime brkn	3793
Total Depth	

Tops:
Lansing Lime 3545

7-5-45 Perf. csg w/12 shots opposite Lansing Lime formation from 3637-47 - hole filled 215' w/wtr in 25 mins.

7-10-45 Set packer @ 3613 & squeezed perforations from 3637-47 w/160 sacks of cement under 2000# press. 80 sacks went into formation.

7-17-45 Perf. csg from 3780-90 w/12 shots; from 3762-70 w/12 shots & from 3741-45 w/10 shots. No show of oil or water.

7-18-45 Perf. csg as follows: 3741-49 w/22 shots-no show of oil; 3722-32 w/24 shots hole filled 300' w/oil in 1 hr; 3708-98 w/24 shots-hole filled 2250' w/oil in 5 hrs.

~~7-20-45 Perf. csg 22-3000 for 3 hrs off bottom.~~

7-20-45 Estab. Temp. Pot. by swbg 96 BO in 3 hrs. Est. Pot. 800 B

Note: All depths are calculated from derrick floor except formation log which is calculated from the rotary table.