

15-179-05277

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


2-6-27w

Company - CONTINENTAL OIL CO.  
Farm - W. C. Carlton No. 1.

SEC. 2 T. 6 R. 27 W  
NE SW SW  
990'N & 990'E of SW/4

Total Depth. 3815 PB 3784  
Comm. 11-4-44 Comp. 1-1-45  
Shot or Treated.  
Contractor.  
Issued. 2-24-45

County. Sheridan  
KANSAS



CASING:  
10 3/4" 241' Cem.  
6" 3794' Cem.

Elevation. 2562

Production. Pot. 25 B Temp Min

Figures Indicate Bottom of Formations.

sand & shale	0-250
shale & shells	1360
lime brkn	1707
salt, shale & shells	2082
shale & shells	2327
lime brkn	2727
lime	2956
lime brkn	3011
lime	3815
Total Depth (PB 3784)	

Top of Lansing Lime 3568

12-22-44 Drilled cement to  
3784'; ran radioactivity  
log; perf 6" OD csg w/Lane-  
Wells gun perf as follows:  
3609-3624' w/48 shots; 3650-  
3658' w/24 shots; 3702-3710'  
w/24 shots; 3735-3753' w/58  
shots; hole filled 1850' w/  
oil in 8 hrs

12-23-44 Swbd 15 bbls Oil  
PH for 4 hrs off bottom

12-27-44 Ripped 6" OD csg  
3579-3606'; hole filled  
3700'w/oil

12-28-44 Swbd 19 BOPH for  
4 hrs off bottom

12-29-44 Swbd 50 BO in  
2 hrs to estb a 25 B min  
temp pot  
PBTD 3784 in Lansing lime

Note: Footages calculated from  
pumping derrick floor level,  
except formations.