


Company - CONTINENTAL OIL CO.  
 Farm - A.M. Bouts No. 1.

11-6-270

SEC. 11 T. 6 R. 27 W  
 NW NE NW  
 3 30'S 990' W N $\frac{1}{4}$  Cor.

Total Depth. 3805' PB 3673'  
 Comm. 5-20-44 Comp. 6-6-44  
 Shot or Treated.  
 Contractor.  
 Issued. 10-28-44

County. Sheridan  
 KANSAS



CASING:  
 10 $\frac{3}{4}$ " 238' Cem.  
 6" 3738' Cem.

Elevation. 2575

Production. Pot. 587 B.  
 12 BW

Figures Indicate Bottom of Formations.

rock	0-6
shale	60
sand	75
shale	170
shale & shells	210
lime brkn	250
shale & shells	2017
lime brkn	2130
lime	2200
lime brkn	2443
shale & shells	2630
lime	2837
lime brkn	2895
lime	3378
lime brkn	3454
lime	3760
shale	3780
lime	3805
Total Depth	

6-23-44 Drilled out cem to 3673  
 6-26-44 Perf 6"OD casing w/36  
 shots, fr 3605 -3628 ,w/Lane-Wells  
 gun perforator - hole filled 1100'  
 w/oil in 1 hr., & 2600' w/oil in 8 hrs.  
 8-25-44 Established 24 hr. physical Pot.  
 of 587 bbls. oil & 12 bbls. wtr  
 P.B.T.D. 3673' in KC Lime-  
 producing fr KC Lime

Note: Footages calculated fr  
 pumping DFL, except formations

P.B. 3673

Top of KC Lime 3603

6-11-44 Perforated 6"OD casing w/35  
 shots, from 3690'-3708', w/Lane-Wells  
 gun perforator - hole filled 600' w/wtr

6-13-44 Dumped 5 sx of Portland Dewey  
 cem on bottom, plugging back to 3694

6-14-44 Dumped 2 sx of Monarch cem.  
 on bottom, plugging back to 3682  
 Cem. did not set. Cleaned out cem.

6-15-44 Perforated casing w/11 shots,  
 fr 3659'-3669', w/Lane-Wells gun perf.  
 hole filled 75' w/wtr, no oil, in 20 mins.  
 Bailed hole dry

6-18-44 Dumped 7 sx of Portland Ideal  
 cem. on btm, plugging back to 3647  
 Cem. did not set. Cleaned out cem. &  
 dumped 3 more sx