

15-179-05261

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


11-6-27W

Company - DERBY OIL CO, PEEL-HARDMAN ETAL
Farm - Bouts No. 1

SEC. 11 T. 6 R. 27W
NE SE NW

Total Depth. 3837
Comm. 2-7-49 Comp. 3-23-49
Shot or Treated.
Contractor. Glenn Peel Drlg. Co.
Issued. 4-16-49

County. Sheridan
KANSAS



Elevation. 2603 Ind.

Production. dry

CASING:

8 5/8" 294' cem
5 1/2" 3836' cem.

Figures Indicate Bottom of Formations.

sand, shale	294
shale	1155
sand	1323
shale, shells	1665
anhydrite	1750
shale, shell brks	2190
lime	2225
shale	2355
shale, shells	2555
shale, lime	3010
lime	3115
lime, shale	3580
lime	3690
lime, shale	3732
lime cherty	3755
lime	3820
lime cherty	3837
Total depth	

Tops:

Heebner	3593
Lansing	3633

Moved in cable tools 2-19-49,
started bailing. Bailed to bottom
ran Lane Wells log 2-22-49. Perforated
18 shots from 3679-85'. Swbd 20 BWPB
w/oil stains. Set Lane Wells plug at 3672'.
Perforated from 3662-3668'. Filled up 575'
water in 30 mins. after shots. Ran tubing
and cemented. Drilled cement to 3678'.
Tested zone from 3662-66'. Making about
1 BWPB. Tested zone from 3679-85', not
making any water. Halliburton retainer @
3634'. Drilled retainer and cement and
tested zone at 3666'. Dry. Shootingw/
Lane Wells 3-19-49. Swbg and testing. Plug
at 3670'. Made 4 BWPB. Set plug at 3661'.
Perforated from 3635-39 and 3618-26, no
show. Acidized w/1000 gals, no help.
Dry and abandoned. Completed 3-23-49.