

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-179-05160
12-6-27W

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Cramer No.1

SEC. 12 T. 6 R. 27W
SW SW NE

Total Depth. 3826'
Comm. 2-19-58 Comp. 3-24-58
Shot or Treated.
Contractor. Imperial Oil of Kans, Inc.
Issued. 5-31-58

County Sheridan
KANSAS



CASING:
8 5/8" 219' cem w/150 sx.
5 1/2" 3826'

Elevation. 2606' RB

Production. 149 BOPD, 10% Wtr.

Figures indicate Bottom of Formations.

surface sand	217
shale & sand	817
shale & shells	1400
Dakota sand	1590
shale & red bed	2168
Anhydrite	2205
shells & shale	2620
shale & lime	3610
lime	3826 RTD
Total Depth	

TOPS:	SAMPLE	WELEX GUARD LOG
Anhydrite	2168	
Heebner	3578	3577
Toronto	3602	3600
Lansing	3617	3617
Base Kansas City	3825	

DRILL STEM TESTS:

- #1 3637-57, open 2 hrs, rec. 60' gas, 30' slightly oil cut mud, 30' oil cut mud, BHP 130#.
- #2 3683-3705, open 1 hr, rec. 10' mud, BHP 15#.
- #3 3696-3732, open 1 hr, rec. 20' mud, BHP 80#.
- #4 3730-55, open 1 hr, rec. 20' mud, BHP 50#.
- #5 3752-85, open 2 hrs, rec. 180' gas, 110' slightly oil cut mud, BHP 390#.
- #6 3781-3826, open 1 hr, rec. 45' mud, BHP 80#.