

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-179-24538
12-6-27W

Company- Imperial Oil of Kansas, Inc.,
Farm- Schoen No. 3

SEC. 12 T. 6 R. 27W
CS $\frac{1}{2}$ NW SE

Total Depth. 3840'
Comm. 9-28-57 Comp. 10-23-57
Shot or Treated.
Contractor. Imperial Oil Of Kansas Inc.,
Issued. 12-28-57

County Sheridan
KANSAS



Elevation. 2622' RB.

Production. 252 BOPD. No Wtr.

CASING:

8 5/8" @ 218' w/175 sks. cem.
5 1/2" @ 3840'

Figures indicate Bottom of Formations

sand & clay	190
shale & shells	1150
sand & pyrite	1315
shale & shells	1420
shale & sand	1560
shale & shells	1745
shale & sand	2065
shale	2130
Anhydrite	2170
shale & shells	2465
shale & lime	3570
lime	3840'
Rotary Total Depth	3840'

TOPS:

Anhydrite	2174
Heebner	3589
Toronto	3612
Top of Lansing	3627
Base of Kansas City	3834
Rotary Total Depth	3840

Drill Stem Test:

- #1 3618-52 (Top of Lansing)
Open 1 hr. Rec. 15' mud. BHP 100#.
- #2 3642-65 (35' zone) Open 1 1/2 hrs.
Rec. 165' heavily oil cut mud.
BHP 350#.
- #3 3681-3707 (90' zone) Open 2 hrs.
Rec. 120' heavily oil cut mud,
30' clean oil. BHP 710#.
- #4 3704-30 (100' zone) Open 2 hrs.
Rec. 720' gas, 180' heavily oil
cut mud. BHP 480#.