

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-179-00105


36-6-27W

Company: IMPERIAL OIL OF KANSAS, INC.
Farm: Sidesinger No. 1

SEC. 36 T. 6 R. 27W
NE SW NE

Total Depth. 4619
Comm. 6-25-55 Comp. 7-11-55
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 8-27-55

County Sheridan
KANSAS



8 5/8 @ CASING:
215' w/ 175 sx cmt.

Elevation. 2686 RB

Production Dry

Figures indicate Bottom of Formations.

surface clay & sand	215
sand, shale & shells	870
shale & clay	1148
shale & shells	1670
Dakota sand & iron	1820
shale & sand	2363
anhydrite	2403
red bed & shale	2520
red bed, shale & shells	2785
shale & lime	3469
lime	4600
Arbuckle	4619
Total Depth	

TOPS:	
Anhydrite	2370
Heebner	3833
Toronto	3857
Lansing	3873
Base KC	4083
Marmaton cherty lime	4171
Cherty conglomerate	4375
Mississippi chert	4421
Mississippi	4440
Viola dolomite	4494
Simpson (?)	4585
Arbuckle	4594

DST #1: 3843-66, open 30 min. rec.
10' mud, BHP 35#/20 min.

DST #2: 3895-3910, open 45 min. rec.
10' mud w/ oil specks, BHP 30#/20 min.

DST #3: 3992-4012, open 30 min. rec.
4' mud, BHP 30#/20 min.