

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

27-6-29W


15-179-00046

Company- WESTPAN HYDROCARBON CO.
Farm- Wessell No. 1

SEC. 27 T. 6 R. 29W
SW NW NW

Total Depth. 4720'
Comm. 12-4-52 Comp. 12-22-52
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 3-21-53

County Sheridan
KANSAS



CASING:

8 5/8" 289' cem.
5 1/2" 4145' com.

Elevation. 2818

Production. 216 Bbls. plus
trace of water

Figures Indicate Bottom of Formations.

top soil & sand	160
sand, shale	220
shale	750
sand, shale	975
shale, shells	1910
sand	1970
shale, shells	2070
Anhyd.	2095
shale, lime	2105
shale, sand	2160
red bed, shale	2510
shale, lime	2535
Anhyd.	2577
shale, shells	2635
red bed, shells	2685
shale, shells	2780
shale, lime	2910
shale, shells	3270
lime	3345
shale, lime	3510
lime	4155
lime, shale	4205
lime	4330
lime, shale	4430
lime, chert	4541
lime	4635
lime, Arbuckle	4715
lime, Arbuckle	4720
Total Depth	

Tops-Scout	
Anhyd.	2170
Topeka	3627
Heebner	3901
Toronto	3928
Lansing	3944
Base K.C.	4153
Mississippi Chert	4448
Miss, lime	4499
Dolo.	4507
Arbuckle	4602