

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

28-6-29w  
15-179-05239  
SEC. 28 T. 6 R. 29W


Company. HENDERSON OIL CO et al.  
Farm. Emigh No. 2

NE NE NE

Total Depth. 4136  
Comm. 10-3-53  
Shot or Treated.  
Contractor.  
Issued. 12-19-53

Comp. 10-23-53

County Sheridan  
KANSAS



CASING:

5/8 @ 256'  
1/2 @ 4135'

Elevation. 2821 RB.

Production. 170 B O

Figures indicate Bottom of Formations.

|                      |      |
|----------------------|------|
| clay & sand          | 215  |
| clay                 | 230  |
| shale                | 256  |
| shale & shells       | 1340 |
| shale, shells & sand | 1850 |
| sand & pyrite        | 1900 |
| shale & shells       | 2290 |
| sand                 | 2380 |
| shale & shells       | 2550 |
| anhydrite            | 2580 |
| shale & shells       | 3305 |
| lime                 | 3352 |
| lime & shale         | 3934 |
| lime                 | 4136 |
| Total Depth          |      |

TOPS:

|         |      |
|---------|------|
| Heebner | 3901 |
| Toronto | 3927 |
| Lansing | 3939 |

CO to 4125 Perf. w/ 16 holes 4114-15  
Squeeze w/ 300 sx, perf w/ 16 holes  
4082-83, squeeze w/ 200 sx Co to 4106  
Perf. w/ 19 holes 4094-4100 Az. w/  
1000 gal Swb 10 BOPH.