

GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

AUG 22 1970

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

35.6.36W
CSE E

Elev. 3277' KB

ROULIER #1

C SE NE Section 35-6S-36W

Thomas County, Kansas

Commenced: August 30, 1969

Completed: September 15, 1969

Dry/Kind.

OPERATOR - Graves Drilling Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	40	Surface clay and sand	
40	322	Sand and shale	Ran 9 joints of 8-5/8" casing, set @ 320' w/300 sacks cement.
322	1755	Shale and sand	
1755	2111	Shale	
2111	2780	Shale and lime	
2780	2868	Shale	
2868	2906	Anhydrite	
2906	2943	Shale	
2943	4175	Shale and lime	
4175	4226	Lime	
4226	4535	Lime and shale	
4535	4805	Lime	
4805	4837	Lime and shale	
4837	4845	Lime, chert and shale	
4845	4881	Lime	
4881	4916	Lime and chert	
4916	4932	Lime	
4932	TD		Dry and abandoned.

anhydrite 2870
new 3448
Heelover 4072
Toronto 4104
LKC 4119
BKC 4400
Miss 4748
Kinderhook 4900

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE NE Section 35-6S-36W, Thomas County, Kansas, to the best of my knowledge and belief.

E. E. HALL