

State Geological Survey
WICHITA, BRANCH

MAY 30 REC'D
WELL LOG

15-181-20087

2-6-37W

COMPANY A. Scott Ritchie

FARM JARVIS-STIVER NO.1

SEC.

2 T. 6 R. 37W

LOC.

C N E N E

RIG. NO. 7

TOTAL DEPTH 4960'

COMM.

11-19-79

COMP.

12-3-79


CONTRACTOR

Murfin Drilling Company

COUNTY

Sherman

KANSAS



CASING

20

10

15

8-5/8" csg. set @ 410' w/300 60-40 posmix,

ELEVATION

12

6 3% Sunst.

13

5

PRODUCTION

4 1/2" csg. set @ 4860' w/275 sx. of 60-40 posmix, 18% salt- 3/4% CFR-2.

FIGURES INDICATE BOTTOM OF FORMATIONS

220'	Top Soil & Sand
230'	Sand
250'	Clay
410'	Blue Shale
555'	Shale
2350'	Shale & Sand
3102'	Shale
3140'	ANHYDRITE
3215'	Shale
3475'	Shale & Lime
3640'	Shale & Lime & Sand
4090'	Lime & Shale
4170'	Lime
4286'	Lime & Shale
4356'	Shale & Lime
4410'	Lime
4448'	Lime & Shale
4722'	Lime
4960'	Lime & Shale R T D