

15-181-05041

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


10-6-37W

Company- PHILLIPS PETROLEUM CO.
Farm- Llanos No. 3

SEC. 10 T. 6 R. 37W
C NE NW

Total Depth. 4950' PB 4657'
Comm. 9-23-58 Comp. 1-8-59
Shot or Treated.
Contractor.
Issued. 4-4-59

County Sherman
KANSAS



Elevation. 3417' DF

Production. 626 BOPD

CASING:

9 5/8" 360' cem w/330 sx.
7" 4844' cem w/95 sx.

Figures indicate Bottom of Formations.

clay & sand	270
sand	290
shale	2190
shale & shells	2690
shale w/lime streaks	2820
shale & shells	3080
Anhydrite	3115
shale w/strks anhy. and red bed	3240
shale w/lime strks	3970
lime & shale	3996
lime & chert	4050
lime	4780
sand & shale	4828
sand, lime & shale	4875
lime & shale	4910
lime	4950
Total Depth	4950*
Plugged back to	4657'

TOPS: SCHLUMBERGER

Anhydrite (scout)	3080
Base Anhydrite (scout)	3115
Howard	4050
Topeka	4075
Heebner	4212
Toronto	4249
Lansing-Kansas City	4269
Drum	4404
Base Lansing-Kansas City	4527
Marmaton	4535
Cherokee	4698
Mississippian	4919

* Producing formation penetrated at 4950'.

Int. Prod: State pot. of 314.42 BOPD,
n/w 16/64" SPM from LKC.
I.P. of 312 BO n/w from Marm. 4582-93 &
LKC perf: 4450-68 w/1500 acid
Marm Perfs: 4643-52, 4582-93