

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-181-05042


10-6-37W

Company- PHILLIPS PETROLEUM CO.
Farm- Llanos No. 4

SEC. 10 T. 6 R. 37W
C NE NE

Total Depth. 5014' PB 4533'
Comm. 11-3-58 Comp. 12-19-58
Shot or Treated.
Contractor.
Issued. 1-17-59

County Sherman
KANSAS



Elevation. 3451' DE

Production. 180 BO & 34 BWPD

CASING:

9 5/8" 374' cem w/330 sx.
7" 4982' cem w/105 sx.

Figures indicate Bottom of Formations.

surface soil, sand, clay	100
shale	210
sand	320
shale & shells	497
shale	1555
shale & shells	2755
shale & lime	2895
Gibson	2905
red bed	3116
Anhydrite	3149
shale & shells	3220
shale & lime	4355
lime	4446
lime & shale	4625
lime	5014

Total Depth
Plugged back to 4533'

TOPS: SCHLUMBERGER

Anhydrite (scout)	3116
Base Anhydrite (scout)	3149
Admire (scout)	3802
Wabaunsee	4884
Maple Hill (scout)	3960
Howard	4089
Topeka	4114
Heebner	4253
Toronto	4289
Lansing-Kansas City	4307
Drum	4442
Base Lansing-Kansas City	4562
Marmaton	4574
Cherokee	4743
Mississippian	4968

Perf. 4486-4503, 1500 acid.
Last hour rec. 12.36 BOPH,
.51/100 BWPH

Perf. 4442-43, rec. 55.38 BO, 11.14 BW
7 hrs.