

15-181-20088  
11-6-37W

# CONTRACTOR'S WELL LOG

OPERATOR: Beren Corporation  
CONTRACTOR: Abercrombie Drilling, Inc.  
WELL NAME: Glasco #1  
LOCATION: SW NW NE, Section 11-6S-37W  
Sherman County, Kansas  
SPUD DATE: November 18, 1979  
COMPLETION DATE: November 29, 1979

0	395	Surface soil, sand and shale
395	900	Shale
900	1350	Shale and sand
1350	1825	Shale
1825	2735	Shale and sand
2735	3125	Shale
3125	3163	Anhydrite
3163	3588	Shale
3588	4490	Lime and shale
4490	5015	Lime
	5015	Rotary Total Depth

Spud hole at 11:00 a.m., November 18, 1979. Drilled 394' of 12 $\frac{1}{4}$ " hole. Ran 9 joints of 8-5/8" used 28# casing. (Talley 386') Set at 393' R.B. with 300 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 4:45 p.m., November 18, 1979.

T.D. 5015'. Set 1st plug at 1900' with 70 sacks, 2nd plug at 380' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and 5 sacks in the rat-hole. Cemented with 50/50 posmix, 6% gel. Plug was down at 6:00 a.m., November 29, 1979.

## SAMPLE TOPS:

Anhydrite 3125'  
B/Anhydrite 3163'