

DAILY DRILLING REPORT

PI 13-6-37W



PROSPECT Lyman YEAR 1981
 LEASE Lyman WELL NO. 1 WELL LOCATION NE NE NW COUNTY Shelby STATE KS
 ALL SITE LEASE DESCRIPTION Sec. 13-6S-37W API#

OPERATOR Beren Corporation
 CONTRACTOR Murfin Drilling Company
 GEOLOGIST Rene Stucky
 DEVELOPMENT WELL PROSPECT TEST WELL X
 OWNERSHIP 1981 Beren Program

ELEVATION: GR 3399
 DF
 KB 3404
 NOTIFY Petroleum Incorporated
800 R.H. Garvey Building
300 West Douglas
Wichita, Kansas 67202
Jan 261-5235

IDENTIFICATION Test Well
(\$3.00/ft support from
Petroleum, Inc.)

TOPS: Anhydrite 3079 (+ 325)
 Base Anhydrite 3117 (+ 290)
 WAB 3861 (-457)
 TOP 4074 (-670) -20'
 HLS 4240 (-836)
 LKC 4393 (-888) -20'

Charles F. Domily, Fred B. Dicke
 P.O. Box 1686
 Ft. Worth, Texas 76101

Muncie Crk 4410 (- 1006) - 11'
 STK 4492 (- 1088) - 13'
 BKC 4542 (- 1138) - 13'
 Marm 4612 (- 1208) - 12'

MOVING IN & RIGGING UP October 5, 1981 SPUD October 6, 1981

SET 8-5/8" @ 362' w/ 300 sx 60-40 pozmix, 2% gel, 3% CC. P.D. 6:30 PM 10-6-81.
D.O. 12:30 AM 10-7-81. Circulated by Sun.

DATE DEPTH DST

Sample Tops Cont'd

10/7/81	1370'	Pawnee	4647 (-1270)	#1	4436-4530 (I,J,K)
		FS	4732 (-1329)	-10'	45/60/45/60
10/8/81	2865'	CK	4757 (-1353)	-5'	Strong blow
					Rec: 780' total fluid
10/9/81	3475'				660' MC oil
10/10/81	4137'				120' HOCM (40% oil)
10/11/81	4450'				1296/1276 132/254 304/376
10/12/81	4530'	An	3078		
10/13/81	4658'	BA	3112 (+ 292)		
10/14/81	4815'	TKO	3952 (- 548)	#2	4535 - 4620 (Pleas - Upper Marm)
10/15/81	4980'	HB	4238 (- 834)		60/60/30/30
		LKC	4292 (- 887)		Rec: 20' mud
		BKC	4555 (-1151)		60/60 71/71 878/618
		MIN	4619 (-1215)		
		PAW	4671 (-1267)		
		FS	4734 (-1330)		
		CK	4762 (-1358)		
		ATOKA	4836 (-1432)		
		MO	4903 (-1499)		
		MISS	4955 (-1551)		
		LTD	4981		
		RTD	4980		

MAY 16 1985

State Geological Survey
 WICHITA BRANCH