


CHAS. M. COATS ET AL
Black No. 1.

SEC.1 T. 6 R.7 W
CNW NE

58784

Total Depth. 3952'
Comm. 12-23-42 Comp. 2-1-43
Shot or Treated.
Contractor. H.B. Mabey Co.
Issued. 2-13-43

County. Mitchell



CASING:
12 1/4" 90'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	80	Hunton lime cherty	3512
shale & shells	265	lime sft porous	3555
sand	340	shale	3586
shale	440	lime Viola	3607
shale & shells	772	lime sft	3612
shale	840	lime	3643
anhydrite	880	dolomite	3645
shale	1200	lime	3695
red bed	1325	lime porous	3720
lime & shale	1380	lime hd	3765
lime	1410	shale green	3767
lime & shale	1480	lime	3850
lime brkn	1830	shale	3853
shale & shells	2121	lime	3860
lime Topeka	2170	shale, lime sand strks	3930
lime brkn	2295	lime Arbuckle	3952
shale red	2300	Total Depth.	
lime brkn	2355		
lime	2380		
shale & lime	2395		
shale red	2420		
shale	2490		
lime Kansas City	2578		
lime oolitic	2609		
lime	2684		
shale	2695		
lime	2700		
lime oolitic	2710		
shale	2718		
lime	2755		
shale	2772		
lime	2798		
lime porous	2810		
shale	2830		
lime	2838		
lime brkn	2853		
lime	2860		
shale sand strks	2900		
shale	2917		
lime	2920		
shale	2943		
lime	2946		
shale	2950		
shale sdy	2973		
shale red	2976		
shale sdy	3000		
Cherokee shale	3050		
shale sdy	3138		
shale red	3142		
shale	3166		
Miss lime cherty	3195		
lime brkn	3205		
lime cherty	3350		
shale (red & blue)	3360		
shale blue	3380		
shale red	3395		