

# State Geological Survey WICHITA BRANCH KANSAS DRILLERS LOG

**IMPORTANT**  
Kans. Geo. Survey request  
samples on this well.


27-7-16W

S. 27 T. 7 R. 16 ~~NE~~ W

Loc. SE NW SW

County Rooks

640 Acres  
N



Locate well correctly

Elev.: Gr. 1857

DF 1859 KB 1862

API No. 15 — 163 — 20,496  
County Number

Operator

Petroleum Management, Inc.

Address 1515 Vickers KSB&T Building  
Wichita, Kansas

Well No.

#1

Lease Name

Stackhouse "B"

Footage Location 1650' South 990' West  
feet from (N) (S) line feet from (E) (W) line

Principal Contractor

Red Tiger Drilling Company

Geologist

William H. Petersen

Spud Date

7-6-73

Total Depth

2864'

P.B.T.D.

--

Date Completed

Abandoned-7-30-73

Oil Purchaser

---

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

| Purpose of string | Size hole drilled | Size casing set (in O.D.) | Weight lbs/ft. | Setting depth | Type cement | Sacks | Type and percent additives |
|-------------------|-------------------|---------------------------|----------------|---------------|-------------|-------|----------------------------|
| Surface Csg       | 12-1/4            | 8-5/8                     | 24#            | 205'          | Quick Set   | 175   | 3% Cal. Chloride           |
| Prod. Csg         | 7-7/8             | 4-1/2                     | 9.5#           | 2801'         | Quick Set   | 50    | --                         |
|                   |                   |                           |                |               |             |       |                            |
|                   |                   |                           |                |               |             |       |                            |

## LINER RECORD

## PERFORATION RECORD

| Top, ft. | Bottom, ft. | Sacks cement | Shots per ft. | Size & type | Depth interval |
|----------|-------------|--------------|---------------|-------------|----------------|
|          |             |              |               | NONE        |                |
|          |             |              |               |             |                |
|          |             |              |               |             |                |

## TUBING RECORD

| Size | Setting depth | Packer set at |  |  |  |
|------|---------------|---------------|--|--|--|
|      |               |               |  |  |  |
|      |               |               |  |  |  |



## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

| Amount and kind of material used | Depth interval treated |
|----------------------------------|------------------------|
| 250 gal 15% Non E                | 2810'                  |
| 1,000 gal 15 % Non E             | 2810'                  |
|                                  |                        |
|                                  |                        |

## INITIAL PRODUCTION

|                                                    |                  |                                                     |                        |                           |
|----------------------------------------------------|------------------|-----------------------------------------------------|------------------------|---------------------------|
| Date of first production<br>NONE                   |                  | Producing method (flowing, pumping, gas lift, etc.) |                        |                           |
| RATE OF PRODUCTION<br>PER 24 HOURS                 | Oil<br><br>bbls. | Gas<br><br>MCF                                      | Water<br><br>bbls.     | Gas-oil ratio<br><br>CFPB |
| Disposition of gas (vented, used on lease or sold) |                  |                                                     | Producing interval (s) |                           |

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                             |                                                                      |                |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------|----------------|
| Operator PETROLEUM MANAGEMENT, INC.                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                             | DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:             |                |
| Well No. #1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Lease Name STACKHOUSE B                                                                                                                                                                                                                                                                                                     | DRY HOLE                                                             |                |
| S 27 T 7 R 16WE<br>W                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                             |                                                                      |                |
| <b>WELL LOG</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                             | SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION. |                |
| Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.                                                                                                                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                             |                                                                      |                |
| FORMATION DESCRIPTION, CONTENTS, ETC.                                                                                                                                                                                                                                                                                                                                                                                                                                                          | TOP                                                                                                                                                                                                                                                                                                                         | BOTTOM                                                               | NAME           |
| Rock & Shale                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 0                                                                                                                                                                                                                                                                                                                           | 220                                                                  | Anhydrite      |
| Shale                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 220                                                                                                                                                                                                                                                                                                                         | 675                                                                  | Base Anhydrite |
| Sand                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 675                                                                                                                                                                                                                                                                                                                         | 850                                                                  | Council Grove  |
| Shale & Redbed                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 850                                                                                                                                                                                                                                                                                                                         | 1166                                                                 | Root Sand      |
| Anhydrite                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 1166                                                                                                                                                                                                                                                                                                                        | 1204                                                                 | Stotler        |
| Shale & Lime                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 1204                                                                                                                                                                                                                                                                                                                        | 1435                                                                 | Topeka         |
| Shale & Lime Streaks                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 1435                                                                                                                                                                                                                                                                                                                        | 1965                                                                 | R.T.D.         |
| Lime & Shale                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 1965                                                                                                                                                                                                                                                                                                                        | 2340                                                                 |                |
| Lime                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 2340                                                                                                                                                                                                                                                                                                                        | 2805                                                                 |                |
| <p><u>DST #1 2515-2580'</u></p> <p>Op 30 min SI 45 min Op 30 min SI 45 min<br/> Initial blow weak, slowly increasing to slightly fair.<br/> Second blow weak to very weak. Recovered 134' rotary<br/> mud--no show. IFP 44 FFP 58 ISIP 924 FSIP 907</p> <p><u>DST #2 2790-2805'</u></p> <p>Op 45 min SI 45 min Op 45 min SI 45 min<br/> Initial blow weak, dead in 13 min. Second flow, no blow.<br/> Recovered 20' oil cut mud, 40' oil specked mud.<br/> IFP 18 FFP 40 ISIP 907 FSIP 640</p> |                                                                                                                                                                                                                                                                                                                             |                                                                      |                |
| USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                             |                                                                      |                |
| Date Received<br>                                                                                                                                                                                                                                                                                                                                                                                           | <div style="text-align: center;"> <br/> Dale Silcott, <span style="font-size: small;">Signature</span><br/> Vice President <span style="font-size: small;">Title</span><br/> 9-28-73 <span style="font-size: small;">Date</span> </div> |                                                                      |                |